John F. Kennedy High School
Baseball, Softball, and Tennis Court Improvements
Sacramento City Unified School District

100% DSA Submittal

October 25, 2023

PREPARED BY:

Project No. 2304200
DSA #02-121752

C. Selectively prune branches as deemed necessary by the Owner's Representative.

3.08 PRUNING REPAIRS

A. Prune and treat damaged area as directed by the Owner's Representative.

3.09 CLEAN-UP

A. Branches, trimmings and debris remaining upon completion of each operation shall become property of the Contractor and shall be promptly removed from the site.

END OF SECTION

SECTION 32 11 00

BASE COURSES

PART 1 - GENERAL

1.01 SUMMARY

A. Section Includes:
1. Grading and compaction of subgrade soil for areas to receive pavement, structures, and base material.
2. Furnishing and placing of aggregate base material.

B. Related Requirements:
1. Section 01 71 23 - Field Engineering
2. Section 31 20 00 - Earth Moving
3. Section 32 12 16 - Asphalt Paving
4. Section 32 13 13 - Concrete Paving

1.02 REFERENCES

A. State of California, Business and Transportation Agency Department of Transportation (Caltrans) "Standard Specifications."

1.03 ADMINISTRATIVE REQUIREMENTS

A. Submittal Procedures: Action submittals shall be submitted in accordance with Section 01 33 00 - Submittal Procedures.

B. Sequencing and Scheduling
1.

SECTION 32 12 16

ASPHALT PAVING

PART 1 - GENERAL

1.01 SUMMARY

A. Section Includes: Asphalt paving is shown on the Drawings and includes, but is not necessarily limited to, the following:
   1. Plant-mixed asphalt and other asphalt items.
   2. Header boards.

B. Related Requirements:
   1. Section 01 33 00 - Submittal Procedures
   2. Section 31 20 00 - Earth Moving
   3. Section 32 11 00 - Base Courses
   4. Section 32 13 13 - Concrete Paving
   5. Section 32 33 00 - Site Furnishings
   6. Section 33 40 00 - Storm Drainage Utilities

1.02 REFERENCES

A. State of California, Business and Transportation Agency, Department of Transportation (Caltrans) "Standard Specifications."

1.03 ADMINISTRATIVE REQUIREMENTS

A. Submittal Procedures: Informational Submittals shall be submitted in accordance with Section 01 33 00 - Submittal Procedures.

B. Sequencing and Scheduling:
   1. Time delay between placement and compaction of base material and installation of asphaltic shall not be more than 5 calendar days. Base material left unpaved longer than this time period shall be subject to testing and re-compaction at the expense of the contractor.

1.04 ACTION SUBMITTALS

A. Product Data: Descriptive literature for primer and other materials prop

PART 2 - PRODUCTS

2.01 DESIGN AND PERFORMANCE REQUIREMENTS

A. At no point shall paved surface fail to drain. Provide drainage as indicated on the Drawings.

B. Asphalt paving shall be free from excessive segregation, defined as gaps between aggregate visible at 3/16 inch or larger, cracking, potholes, raveling, slippage, depressions, corrugations, or other defects at the date of completion and acceptance of the project.

C. Unless otherwise noted, aggregates in asphalt mix may be a blend of virgin material and reclaimed asphalt paving (RAP), with the RAP constituting no more than 15% of the aggregate blend per Section 39 of the Standard Specifications.

D. Asphalt mix for use beneath track surfacing, tennis court surfacing, or other court system to receive surface coating shall consist of only virgin material; RAP shall not be used.

2.02 ASPHALT PAVING

A. Paving Asphalt Binder: Shall be PG 64-10, conforming to Section 92 of the Standard Specifications.

B. Prime Coat: Liquid asphalt to conform to the requirements for SS-1 liquid asphalt as per Section 94 of the Standard Specifications and approved by the Owner's Representative.

C. Tack Coat: Asphaltic emulsion to be penetration type conforming to the RS-1 requirements of Section 94 of the Standard Specifications.

D. Aggregates:
1. Traffic Areas (Vehicular Asphalt Paving): 1/2 inch medium in accordance with the gradation requirements of Section 39 of the Standard Specifications, unless otherwise specified or noted. Traffic area aggregate shall meet Specification 2215.5( )]TJ -21.10189-2.2814 TD - TD -.000

PART 3 - EXECUTION

3.01 EDGEBAND INSTALLATION

A. Install to conform to shapes, lines, cross sections, and grades shown on the Drawings.

B. Radii shall be smooth and constant with properly aligned tangent points.

3.02 PAVING INSTALLATION - GENERAL

A. Conform to requirements of Sections 37 and 39 of the Standard Specifications.

B. Place plastic materials under asphalt paving equipment while not in use to catch and/or contain drips and leaks.

C. Areas shall be paved in sequence and direction to avoid driving loaded trucks on the new asphalt surface.

3.03 PREPARATION – TACK COAT

A. General: Apply tack coat to contact surface of adjacent pavement and concrete curbs.

B. Immediately before applying the tack coat, the full width of surface to be treated shall be swept with a power broom and/or air blast to remove all loose dirt and other objectionable material.
   1. Vegetation shall be removed and an approved herbicide applied to those areas before cleaning.
   2. Emulsified asphalt shall be diluted by the addition of water when directed by the Owner's Representative and shall be applied a sufficient time in advance of the paver to ensure that all water has evaporated before the overlying mixture is placed on the tacked surface.
   3. The bituminous material including vehicle or solvent shall be uniformly applied with a bituminous distributor at the rate of 0.05 to 0.07 gallons per square yard. The type of bituminous material and application rate shall be approved by the Owner's Representative prior to application.

C. Following the application, the surface shall be allowed to cure without being disturbed. The curing period shall be not less than 24 hours, unless otherwise approved by the Owner's Representative, and shall be sufficient to permit drying out and setting of the tack coat.

D. After tack coat has cured, suitable precautions shall be taken by the Contractor to protect the surface against damage prior to placement of next course.

3.04 PLACING ASPHALT PAVEMENT

A. General:
   1. Place asphalt within 48 hours of applying primer or tack coat and after required curing time for emulsions.
   2. Each course of asphalt concrete shall be installed or constructed in accordance with the Standard Specifications Section 39.
   3. All layers, except as otherwise provided in these Specifications, shall be spread with mechanical spreading and finishing equipment as provided in the Standard Specifications Section 39-5.01.

B. Tack and Levelling Course:
   1. After completion of the base course a tack coat shall be applied and a levelling course of minimum 1-inch thickness shall be placed and compacted over entire area.
   2. After compacting, the surface of the leveling course shall be check for compliance with the specified tolerances.

3. Where required, depressions shall be filled with asphalt concrete fines prior to proceeding with subsequent pavement construction and final court surfacing.

C. Paver Equipment Requirements:
1. Asphalt pavers shall be self-propelled mechanical spreading and finishing equipment provided with a screed or strike-off assembly capable of distributing the material to not less than the full width of a traffic lane.
   a. Screed action shall include cutting, crowding, and other practical action which is effective on the mixture without tearing, shoving, or ripping, and which produces a surface texture of uniform appearance.
   b. The screed shall be adjustable to the required section and thickness. The paver shall be provided with a full width roller or tamper or other suitable compacting devices.
2. Asphalt pavers shall be operated to insure continuous and uniform movement of the paver.
3. The asphalt paver shall operate independently of the vehicle being unloaded or shall be capable of propelling the vehicle being unloaded in a satisfactory manner and, if necessary, the load of the haul vehicle shall be limited to that which will insure satisfactory spreading.
4. While being unloaded, the haul vehicle shall be in contact with the machine at all times, and the brakes on the haul vehicle shall not be depended upon to maintain contact between the vehicle and the machine.

D. Placing Hot-Mix Asphalt:
1. The completed mixture shall be deposited at a uniform quantity per linear foot to provide the required compacted thickness without resorting to spotting, pick-up or otherwise shifting the mixture.
   a. Segregation shall be avoided, and the surfacing shall be free from pockets of coarse or fine material.
   b. Asphalt containing hardened lumps shall not be used.
2. Unless lower temperatures are directed by the Owner's Representative, mixtures shall be spread, and the first coverage of initial or breakdown compaction shall be performed, when the temperature of the mixture is not less than 275 degrees F. Breakdown compaction shall be completed before the temperature of the mixture drops below 250 degrees F.
   a. A layer shall not be placed over another layer that exceeds 2 inches in compacted thickness until the temperature of the layer that exceeds 2 inches in compacted thickness is less than 150 degrees F at mid depth.
   b. Layer thickness shall not be less than 1.25 inches or exceed 2 inches unless approved in advance and in writing by Owner's Representative.

E. Construction Joints: Before placing the top layer adjacent to cold transverse construction joints, the cold transverse construction joints shall be cut to a vertical face and to neat line.
1. Transverse joints shall be tested with a 16-foot straightedge and shall be cut back to conform to meet the specified tolerances.
2. Connections to existing surfacing shall be feathered to conform to the requirements for smoothness.
3. Longitudinal joints shall be trimmed to a vertical face and to a neat line if the edges of the previously laid surfacing are, in the opinion of the Owner's Representative, in such condition that the quality of the completed joint will be affected.

F. Rollers and Roller Equipment: The Contractor shall furnish a sufficient number of rollers to achieve the compaction and surface finish required by these Specifications.
1. Each roller shall have a separate operator.
2. Rolling equipment shall be self-propelled and reversible.
3. Rollers shall be equipped with pads and water systems that prevent sticking of asphalt mixtures to the pneumatic- or steel-tired wheels.
4. A parting agent that will not damage the asphalt mixture, as determined by the Owner's Representative, may be used to aid in preventing the sticking of the mixture to the wheels.

G. Compaction:

1. Compact pavement by rolling to specified relative compaction but not less than 96 percent of bulk unit weight tested in accordance with the nuclear gauge or CTM 308 core method.
   a. Do not displace or extrude pavement from position.
   b. Hand compact in areas inaccessible to rolling equipment.
   c. A “pass” shall be one movement of a roller in either direction.
   d. A “coverage” shall be as many passes as are necessary to cover the entire width being paved.
   e. Overlap between passes during a coverage, made to ensure compaction without displacement of material in accordance with good rolling practice, shall be considered to be part of the coverage being made and not part of a subsequent coverage.
   f. Each coverage shall be completed before subsequent coverages are started.
   g. Rolling shall commence at the lower edge and shall progress toward the highest portion.
   h. Perform rolling with consecutive passes to achieve even and smooth finish without roller marks.
2. Asphalt concrete shall be compacted to a relative compaction of not less than 96 percent and shall be finished to the lines, grades, and section shown on the Drawings.
   a. In-place density of asphalt concrete will be determined prior to opening the pavement to public use.
   b. Relative compaction will be determined by California Test 375.
   c. Laboratory specimens will be compacted in conformance with California Test 304.

H. The completed surfacing shall be thoroughly packed, smooth, and free from routes, humps, depressions, or irregularities. Ridges, indentations, or other objectionable marks left in the surface of the asphalt paving by blading or other equipment shall be eliminated by rolling or other means. The use of any equipment that leaves ridges, indentations, or other objectionable marks in the asphalt paving shall be discontinued, and other acceptable equipment shall be furnished by the Contractor.

3.05 TOLERANCES

A. Surface Tolerance:
   1. The Contractor shall have on site a 12-foot straightedge for testing the asphalt paving surface when said straightedge is laid on the finished surface and parallel with the center line, the surface shall not vary more than 0.01-foot from the lower edge of the straightedge.
   2. The transverse slope of the finished surface shall be uniform to a degree that no depressions greater than 0.02-foot are present when tested with a straightedge 12 feet long.
   3. Skin patching will not be allowed to correct depressions.

B. Thickness Tolerance:
   1. The pavement thickness shall be determined by measuring the average thickness of core samples taken from the pavement for density determination.
   2. Thickness will be determined from the cores and shall be based upon the average of the cores.
   3. The asphalt thickness indicated on cross sections shall be maintained.
   4. Thickness deficiencies in excess of 3/8-inch shall be corrected by removal and replacement of overlay at the discretion of the Owner’s Representative.
   5. Skin patches and overlays less than 1-1/2 inches will not be allowed.

C. Adjustments to Contract Sum:
   1. The Contract will be reduced for thickness deficiencies equal to or less than 3/8-inch in proportion to 2 times the percent of thickness deficiencies to the specified pavement thickness (i.e., a 1/4-inch thickness deficiency in a pavement with a 2-inch specified thickness would result in a reduction of the unit price of (2 x 0.25)/2.0 = 25 percent) for the lot containing a thickness deficiency.
   2. No Contract Sum adjustment will be made for thickness in excess of those specified or shown.

3.06 FIELD QUALITY CONTROL

A. Take samples and perform tests in accordance with Caltrans Test Methods.

B. Upon completion of the work, Contractor shall provide a water drainage test for paved areas.
   1. Areas that fail to drain properly, as determined by the Owner's Representative, shall be corrected and repaired at no additional cost.
   2. If repaired, the entire surface shall have a seal coat applied at Contractor's cost.
      a. Type of seal coat will be determined by the Owner's Representative.
      b. Repairs shall be made within 15 calendar days of notification at the expense of the Contractor.

C. Contractor to install asphalt to be flush with top

SECTION 32 13 13

CONCRETE PAVING

PART 1 - GENERAL

1.01 SUMMARY

A. Section Includes: Concrete flatwork as shown on the Drawings including, but is not necessarily limited to, the following
   1. Curbs.
   2. Mowbands and edge bands.
   3. Walkways.
   4. Expansion and control joints.
   5. Reinforcement.
   6. Finishing.

B. Related Requirements:
   1. Section 01 33 00 - Submittal Procedures
   2.

1. Formwork, joint patterns, base material, reinforcement, "dobies," ties, and other installation accessories shall be reviewed and accepted by the Owner's Representative prior to pouring concrete.
2. Forms, reinforcing, and accessories shall be in place and Contractor shall give a minimum of 5 working day lead-time notice to Owner's Representative when scheduling the review request.
3. Contractor shall allow a minimum of 2 working days after pre-pour review in Construction Schedule for possible modifications to concrete preparation work, at no cost or delay to the project.

H. The Owner's Representative shall have access to any off-site batch plant or quarry supplying materials at all times for subject project and truck route to the project site.

I. Mockups:
1. General:
   a. Mix design shall match that used on accepted sample panels and proposed for use in final construction including cement and color additive.
   b. Prepare at least one month before start of final concrete work to allow concrete to cure before observation.
   c. Concrete color and finish for mockup appearance shall match color and finish of accepted sample.
   d. Build mockups at the location indicated or, if indicated, as selected by the Owner's Representative
   e. Notify Owner's Representative 5 working days in advance of dates and times when mockups will be constructed and layout will be ready for review.
   f. Color and texture shall be approved before starting construction.
   g. Perform specified slip-resistance testing on mockups.
   h. Maintain final accepted mockups in an undisturbed condition as a standard for judging the completed Work.
   i. Retain samples of sands, aggregates, and colorants used in the mockups for comparison with materials used in final work.
   j. Demolish and remove mockups when directed if not incorporated into the final work.
2. Flat Paving Mockups:
   a. 4-feet x 4-feet sample panels of colored concrete flatwork and concrete darken6(x 48(o)nd concren7.26

PART 2 - PRODUCTS

2.01 BASE MATERIALS

A. Aggregate: As specified in Section 32 11 00 - Base Courses.

2.02 FORMS

A. Form Materials: Plywood, metal, metal-framed plywood, or other approved panel-type materials to provide full-depth, continuous, straight, and smooth exposed surfaces.
   1. Use flexible or uniformly curved forms for curves with a radius of 100 feet or less.
   2. Do not use notched and bent forms.

B.

D. Fine aggregates: Fine Aggregate shall conform to ASTM C33.

E. Water: Clean and not detrimental to concrete.

2.05 CONCRETE ADDITIVES

A. Pigment for Concrete: Synthetic mineral-oxide pigments or colored water-reducing admixtures, color

2. Refer to layouts on the Drawings for location of each joint type.

B. Expansion Joints: Install to full depth of slab.
1.

C. One additional test cylinder will be taken during cold weather concreting, cured on job site under same conditions as concrete it represents.

D. At a minimum one slump test will be taken for each set of test cylinders taken.

E. Tolerances:
   1. Vertical deviation from specified grades shall not exceed 0.04 foot.
   2. Surface smoothness deviations shall not exceed 1/8 inch in 8 feet, in any direction.
   3. Thickness shall not be more than 0.01 foot less than planned thickness at any point.

3.13 CURING AND PROTECTION

A. ^èã6Zà ä Ów À e-Þ1†~èg gÖìègç o†~V‘ YÐ œ -÷fñ‡l‰.0 $ Î¬^ê¦'"˜?ì ˜ä1 (–Ð Œ 1ø @ÐÀ 0

SECTION 32 18 00

MISCELLANEOUS PAVING AND SURFACING

PART 1 - GENERAL

1.01 SUMMARY

A. Section Includes: Miscellaneous paving and surfacing as shown on the Drawings, including, but not limited to, the following:
   1. Infield fines mix with sports field conditioner.
   2. Infield fines mix.
   3. Infield clay mix; bag and brick material.

B. Related Requirements:
   1. Section 32 33 00 - Site Furnishings
   2. Section 31 20 00 - Earth Moving
   3. Section 32 11 00 - Base Courses

1.02 ADMINISTRATIVE REQUIREMENTS

A. Submittal Procedures: Action and informational Submittals shall be submitted in accordance with Section 01 33 00 - Submittal Procedures.

B. Sequencing and Scheduling:
   1. Coordinate applicable subgrade preparations, installations of base course materials, and all other work with work of this Section to insure a proper, timely installation.

1.03 ACTION SUBMITTALS

A. Samples:
   1. Unless otherwise specified, submit quart size samples of the following:
      a. Infield fines mixture.
      b. Infield clay mixture.

1.04 QUALITY ASSURANCE

A. Materials Source: Sources of materials specified herein shall not be changed during course of work without review and written acceptance by the Owner's Representative.

1.05 WARRANTY

A. Manufacturers: Provide Owner with the following manufacturers extended warranties.
   1. Poured in Place Rubber Resilient Surfacing: 10 years.
   2. Wood Chip Loose Fill Resilient Surface: 25 years.

PART 2 - PRODUCTS

2.01 SAND AND CLAY MATERIALS

A. Supplier: TMT Enterprises, Inc., San Jose, CA, 408-432-9040 as specified and the basis of design unless otherwise noted, or equal. Contact: Matt Moore.

B. Infield Fines and Clay Mix for Warning Track: "Pac -Bell 2.0 Infield Fines."
   1. Mix shall be free of rocks, debris, vegetation, clay balls, foreign materials, etc. Infield mixes shall be sterilized to eliminate the possibility of any growth of vegetation.
   2. The composition of the mix shall be achieved using mechanical blending equipment prior to delivery to the site and shall be as follows:

Sieve Size	Percent Retained by Weight
4 mm	0
2 mm	3.4
1 mm	14.4
0.5 mm	22.5
0.25 mm	11.3

SECTION 32 18 23

TENNIS COURT SURFACING

PART 1 - GENERAL

1.01 SUMMARY

A. Section Includes: Installation of acrylic surfacing for asphalt tennis courts required for proper completion of the work including, but not necessarily limited to, the following:
   1. Patching and filling cracks.
   2. Tennis court surfacing installation.
   3. Other applicable Project components.

1.02 RELATED SECTIONS

A. Related Requirements:
   1. Section 32 12 16 - Asphalt Paving
   2. Section 32 33 00 – Site Furnishings

B. References
   1. National Asphalt Paving Association (NAPA)
   2. United States Tennis Association (USTA)
   3. International Tennis Federation (ITF)
   4. American Sport Builders Association (ASBA)

1.03 QUALITY ASSURANCE

A. Surfacing shall conform to the guidelines of the ASBA for planarity.

B. All surface coatings products shall be supplied by a single manufacturer.

C. The contractor shall record the batch number of each product used on the site and maintain it through the warranty period.

D. The contractor shall provide the inspector, upon request, an estimate of the volume of each product to be used on the site.

E. The installer shall be an authorized applicator of the specified system.

F. The manufacturer's representative shall be available to help resolve material questions.

1.04 SUBMITTALS

A. Manufacturer specifications for components, color chart and installation instructions.

B. Authorized Applicator certification from the surface system manufacturer.

C. ITF classification certificate for the system to be installed.

1. Over a properly repaired surface of asphalt on existing courts, apply one coat of Acrylic Resurfacer according to the following mix:
   a. Acrylic Resurfacer 55 gallons
   b. Water 20 - 40 gallons
   c. Sand 600-800 pounds / 60-80 mesh
   d. Liquid Yield 112-138 gallons

2. On new asphalt, two coats of Acrylic Resurfacer shall be used to properly fill all voids in the asphalt surface. Use clean, dry 50-60 mesh sand and clean, potable water to make mixes. The

3.06 CLEAN UP

A. Remove all containers, surplus materials, and debris. Dispose of materials in accordance with local, state, and Federal regulations.

B. Leave site in a clean and orderly condition.

END OF SECTION

SECTION 32 31 13

CHAIN LINK FENCING

PART 1 - GENERAL

1.01 SUMMARY

A. Section Includes: chain link fencing improvements shown on the Drawings including, but not necessarily limited to, the following:
   1. Galvanized chain link fabric, posts, gates, and hardware.
   2. Dugouts with metal roofs
   3. Chain link fence with integrally woven privacy plastic slats.
   4. Baseball / Softball backstop(s) with baseboards.
   5. Batting cage(s) with metal roof and interior netting.
   6. Concrete footings and mow bands.

B. Related Requirements:
   1. Section 01 33 00 - Submittal Procedures
   2. Section 09 91 15 - Exterior Site Painting
   3. Section 32 33 00 - Site Furnishings
   4. Section 32 32 15 - Landscape Concrete
   5. Section 32 90 00 - Planting
   6. Structural Drawings

1.02 REFERENCES

A. American Society for Testing and Materials (ASTM):
   1. A53/A53M - Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless.
   2. A123/A123M - Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products.
   3. A392 - Standard Specification for Zinc-Coated Steel Chain-Link Fence Fabric.
   4. F567 - Standard Practice for Installation of Chain-Link Fence."
   5. F1043 - Standard Specification for Strength and Protective Coatings on Steel Industrial Chain Link Fence Framework.
   6. F1083 - Standard Specification for Pipe, Steel, Hot-Dipped Zinc-Coated (Galvanized) Welded, for Fence Structures.

B. American Welding Society (AWS):
   1. A2.4: "Symbols for Welding, Brazing and Nondestructive Examination."

C. Chain Link Fence Manufacturers Institute (CLFMI): Product Manual CLF-PM0610.

D. Industrial Steel Guide for Fence Rails, Posts, Gates and Accessories.

E. State of California, Business and Transportation Agency, Department of Transportation (Caltrans) "Standard Specifications."

1.03 ADMINISTRATIVE REQUIREMENTS

A. Submittal Procedures: Action and Informational Submittals shall be submitted in accordance with Section 01 33 00 - Submittal Procedures.

B. Sequence and Scheduling: Contractor shall coordinate construction timing of chain link fencing and related work with installation of concrete work specified in Section 32 32 15 – Landscape Concrete and all other work.

1.04 ACTION SUBMITTALS

A. Shop Drawings: To scale drawings showing all different types and sizes of backstop units, gates, and fencing systems.
   1. Shop Drawings shall include, but may not be limited to:
      a. All information regarding clearances, connections, components and any miscellaneous related appurtenances (such as wood baseboards at backstops, locking mechanisms etc.).
      b. Concrete footing and reinforcement information.
   2. Indicate materials, dimensions, sizes, weights and finish of components. Include plans, elevations, sections and other required installation and operational clearances, connections, components and miscellaneous related appurtenances such as wood baseboards at backstops and locking.
   3. Show required field measurements and interface with work of other Sections. Provide details showing interface and anchorage of fencing and gates with adjacent construction, both new and existing.
   4. Details showing post anchorage, attachment and bracing. Provide setting drawings, templates, instructions, and directions for installation of anchorage devices.
   5. Details of gates and hardware.
   6. Welds, both shop and field, shall be indicated by AWS "Symbols for Welding, Brazing and Nondestructive Examination," A2.4.

B. Product Data: Manufacturer's descriptive literature for materials and components of the chain link fencing system including coatings, fittings, and hardware.
   1. Include the manufacturer's name and catalog number for each item where applicable.
   2. Clearly identify which portions of the information on the printed literature are applicable if more than one product is shown.

C. Samples:
   1. Chain-link fabric, approximately 12 inches square, if requested by Owner's Representative.
   2. Hardware and fittings Owner's Representative.
   3. Sample of privacy slat system.

1.05 INFORMATIONAL SUBMITTALS

A. Installation Instructions and/or Drawings: Submit as applicable.

1.06 QUALITY ASSURANCE

A. Welding:
   1. Qualifications: Certified and qualified in accordance with AWS D1.1.
   2. Procedures and operations shall comply with AWS "Standard for Welding Procedure and Performance Qualifications," B2.1.
   3. Comply with AWS publication "Welding Zinc Coated Steel" for galvanized products.
   4. Welding inspector's qualifications shall be in accordance with AWS D1.1.

PART 2 - PRODUCTS

2.01 DESIGN AND PERFORMANCE CRITERIA

A. Except as otherwise specified, comply with Chain Link Fence Manufacturers Institute (CLFMI) Product Manual.

B. Industry Standards: Materials and installation shall conform to the requirements of the Chain Link Fence Manufacturers Institute (CLFMI) "Product Manual."

C. Regulatory Requirements: Pedestrian gates and latch hardware shall comply with applicable codes, including provisions for accessibility required by CBC Chapters 10 and 11B, Part 2; and the Americans with Disabilities Act (ADA) and Standards for Accessible Design.

D. Bottom 10 inches of pedestrian gates shall have a smooth uninterrupted surface.

2.02 MATERIALS

A. Fabric: Galvanized steel wire complying with ASTM A392, Class 1, with not less than 1.2 ounce zinc coating per square foot.
1. Selvage: Knuckled finish top and bottom.
2. Steel Fabric: Comply with Chain Link Fence Manufacturers Institute (CLFMI) Product Manual. Furnish one-piece fabric widths for fencing up to 16 feet high. Wire sizes includes zinc coating.
3. Mesh Opening: 2 inches.
4. Wire Diameter: 9-gauge (0.148-inch diameter), unless noted otherwise.

B. Framework: Posts and rails shall be Schedule 40 pipe complying with or conforming to ASTM F1083, Regular Grade, 30,000 psi Yield Strength, or ASTM F1043, Group 1-C, High Strength Grade 50,000 psi Yield Strength, galvanized with not less than 1.8 ounces of zinc coating per square foot of surface area complying with ASTM A123.
1. Strength requirements for posts and rails shall conform to ASTM F1043 or F1083 as noted below.
2. Pipe shall be straight, true to section, material, and sizes specified, and shall conform to the following weights per foot:

NPS in inches	Outside Diameter (OD) in inches	Type 1 Steel ASTM F1083 (30 KSI)	Type II Steel ASTM F1043 (50 KSI)
1	1.315	1.68	1.35
1.25	1.660	2.27	1.84
1.5	1.900	2.72	2.28
2	2.375	3.65	3.12
2.5	2.875	5.79	4.64
3	3.500	7.58	5.71
3.5	4.000	9.11	6.56
4	4.500	10.79	---
6	6.625	18.97	---
8	8.625	28.55	---

5. Tension Bars: Hot-dip galvanized steel with minimum length 2 inches less than full height of fabric, minimum cross-section of 3/16 inch by 3/4 inch and minimum of 1.2 ounce zinc coating per sq. ft. of surface area.
6. Tension Clips: Minimum 3/4 inch wide 12-gauge (.105 inch) thick with finish to match fabric.
7. Truss Rods: Hot dipped galvanized steel rods with minimum diameter of 5/16 inch (7.9 mm).

D. Hardware for Swinging Gates:
   1. General:
      a. Hardware shall be of adequate size and strength to provide proper operation of gates.
      b. Provide hinges, latching and locking devices, and other hardware as shown on the Drawings or required for a complete operable installation.
   2. Hinges: Master Halco heavy duty, or acceptable equal.
   3. Self-closing Hinges:
      a. For gates up to 330 lbs and 5-feet wide:

C.

2. Comply with applicable AWS specification for procedures of manual shielded metal arc welding, for appearance and quality of welds, and for the methods used in correcting welding work.
3. Repair zinc coating damaged by field welding as specified for shop welding.

N. Bolts shall be cut back to within three threads of the nut.

3.03 GATE INSTALLATION

A. Install gates as shown on the Drawings in accordance with reviewed submittals.

B. Cut, drill, and fit as required for installation.

C. Set work accurately in location, alignment, and elevation; plumb, level, and true; and free of rack; measured from established lines and levels.

D. Adjust items prior to securing in place so as to ensure proper matching of components and correct alignment.

E. Field weld all gate hinges in place once gates are aligned and approved by owners representative.

3.04 ADJUSTMENT AND TOUCH-UP

A. Inspect installed work. Verify that gates, latch and hardware operate properly. Correct deficiencies.

B. Restore products and finishes damaged during installation and construction in a manner so that no evidence of correction work remains.

END OF SECTION

SECTION 32 32 00

LANDSCAPE CONCRETE MASONRY

PART 1 - GENERAL

1.01 SUMMARY

A. Section Includes:
   1. Concrete unit masonry at home dugout walls.
   2. Mortar and grout.
   3. Reinforcement for masonry.

B. Related Requirements:
   1. Landscape Concrete: Section 32 32 15; concrete footings.
   2. Exterior Site Painting: Section 09 91 15; painting of masonry.

1.02 ADMINISTRATIVE REQUIREMENTS

A. Submittal Procedures: Action and informational Submittals shall be submitted in accordance with Section 01 33 00 - Submittal Procedures.

B. Coordinate with other Sections for work to be installed in conjunction with concrete unit masonry.

1.03 ACTION SUBMITTALS

A. Shop Drawings: To-scale drawings to illustrate detailing, fabrication, bending and placement of unit masonry reinforcing bars.
   1. Comply with ACI 315 showing bar schedules, stirrup spacing, diagrams of bent bars and arrangements of masonry reinforcement.
   2. Indicate location of conduit, plumbing and other items embedded in unit masonry walls in coordination with placement of reinforcement.

B. Samples for Verification:
   1. Full-size units for each exposed decorative CMU unit other than gray, smooth-faced, units.

C. Mix Designs:
   1. Verification of mortar strength and governmental approval if other than proportion specifications included in CBC Table 21-A are to be used.
   2. Verification of grout strength if other than proportion specifications included in CBC Table 21-B are to be used.

1.04 INFORMATIONAL SUBMITTALS

A. Mill test reports for all reinforcing steel.

B. Certificates:
   1. Material certificates for the following signed by the manufacturer and the Contractor certifying that each material complies with requirements and standards specified.
      a. Each material and grade of reinforcing bars.
      b.

C. Extreme Weather Procedures: Cold and hot-weather construction procedures evidencing compliance with requirements specified in ACI 530.1 and these Specifications.

1.05

2.05 MORTAR AND GROUT MIXES

A. General:
1. Accurately measure materials for mortar and grout in suitably calibrated devices. Measurements based on dry loose volume. Shovel measurements or fractional sack batches not acceptable.
2. Place sand, cement, and water, in that order, in mixer and mix for at least two minutes.
3. For mortar, add lime and continue mixing for at least 10 more minutes or as much longer as required to secure a uniform mass.
4. Retemper mortar only by adding water into a basin made with mortar. Work mortar carefully in.
5. Remove from work any mortar or grout which has not been used within one hour after initial mixing.
6. Proportion grout by volume with sufficient water added to produce consistency for pouring without segregation.
7. Do not use calcium chloride in mortar or grout.
8. Admixtures: Add in accordance with admixture manufacturer's instructions and if included in the approved mix design.

B. Mortar Mix: In compliance with CBC requirements and ASTM A270, Type S for regular grade block.

C. Grout Mix: In compliance with CBC requirements and ASTM C476.

D. Design Strengths:
1. Mortar: Not less than 1,800 psi at 28 days.
2. Grout: Not less than 3,000 psi at 28 days.

PART 3 - EXECUTION

3.01 REINFORCING STEEL

A. Place reinforcement in accordance with ACI 530.1, supported and secured against displacement, with 1/2-inch minimum clearance from the interior face of the masonry unit.

B. Maintain position within 1/2-inch of true dimension.

C. Verify reinforcement is clean, free of scale, dirt, or other foreign coatings which would reduce bond to grout.

3.02 MORTAR BEDS

A. Hollow Units: Provide full mortar coverage on horizo

D. Pattern: Lay masonry in running bond, with vertical joints located at center of masonry units above and below. Align vertical cells for continuity of reinforcement and grout. Course one block unit and one mortar joint to equal 8-inches. Make vertical and horizontal joints equal and of uniform thickness.

E. Horizontal and Vertical Face Joints:
1. Nominal thickness: 3/8-inch, uniform.
2. Tooling: Tool joints when thumbprint hard with joints to compress mortar to ensure full contact with block surfaces.
3. Concealed joints: Flush.
4. Exposed joints: Flush.
5. Internal cleaning: Remove mortar protruding into cells of cavities to be reinforced or filled.

F. Intersections and Corners: Fully bond intersections, external and internal corners.

G. Joining Masonry Work: Provide expansion joints in accordance with reference standards. When joining fresh masonry to set or partially set masonry construction, clean exposed surface of set masonry and remove loose mortar prior to laying fresh masonry.

H. Cold Joints: If necessary, to stop off a horizontal run of masonry, rack back one-half block length in each course. Do not use toothing joint in new masonry to set or partially set masonry when continuing a horizontal run.

I. Cleaning: Remove excess mortar before mortar sets. Clean surfaces at exposed masonry to present even surface texture and color.

3.04 BUILT-IN WORK

A. Avoid cutting and patching. Coordinate placement of built-in products specified in other Sections so built-in products are place as masonry is laid.

B. Install bolts, anchors, nailing blocks, sleeves, inserts, ties, flashings, conduit, and other built-in products as masonry progresses. Install bolts in lead to assure proper alignment and location.

C. Solidly grout spaces around built-in products.

3.05 GROUTING

A. Grout all cells of masonry units which contain reinforcing bolts, etc., all cells below grade, and as specified on the Drawings. Work grout into cores and cavities to eliminate voids. Do not displace reinforcing steel when placing grout.

B. Inspection Holes: Provide inspection and cleanout holes at base of vertical cells for grout lifts in excess of 5 feet. Clean concrete grout spaces of excess mortar and debris before grouting.

C. Construction Joints: When grouting is halted for one hour or longer, form horizontal construction joints by stopping the pour of the grout 1-1/2 inches below top of uppermost unit.

D. After inspection of concrete grout spaces, plug cleanout holes with masonry units. Brace against wet grout pressure.

3.06 PROTECTION OF WORK

A. Protect sills, ledges and offsets from mortar drippings or other damage during construction. Remove misplaced mortar or grout immediately.

B. Cover top of walls with non-staining waterproof coverings when Work is not in progress.

3.07 CURING

A. In hot, dry conditions, CMU shall be fogged during a 3-day curing period at least twice a day.

3.08 POINTING AND CLEANING

A. At final completion of unit masonry work, fill holes in joints and tool.

B. Cut out and re-point defective joints.

C. Dry brush masonry surface after mortar has set, at end of each day and after final pointing.

D. Leave masonry and surrounding surfaces clean and free of mortar spots and droppings.

END OF SECTION

SECTION 32 32 15

LANDSCAPE CONCRETE

PART 1 - GENERAL

1.01 SUMMARY

A. Section Includes:
1. Architecturally exposed formed concrete.
2. Natural site concrete at utility pads.
3. Subgrade, natural, as-cast concrete for foundations, landscape fencing, furnishings and other site improvements.

B. Related Requirements:
1. Section 31 20 00 - Earth Moving
2. Section 32 13 13 - Concrete Paving
3. Section 32 33 00 - Site Furnishings

1.02 REFERENCES

A. State of California, Business and Transportation Agency, Department of Transportation (Caltrans) "Standard Specifications."

1.03 ADMINISTRATIVE REQUIREMENTS

A. Submittal Procedures: Action and Informational Submittals shall be submitted in accordance with Section 01 33 00 - Submittal Procedures.

B. Pre-Installation Meeting: Conduct meeting at Project with Owner's Representative and concrete installer at site to review scope of landscape concrete work and expectations.
1. Meeting shall be scheduled after approval of mockups and sufficiently in advance of commencement of architecturally exposed concrete for the site improvements.
2. Record discussions of conference and any conflict, incompatibility, or inadequacy. Furnish a copy of record to each participant.

C. Coordination:
1. Coordinate delivery so that mixes may be immediately placed upon arrival at site.
2. Coordinate proper installation of accessories and anchorage embedded in concrete and for the provision of holes, openings, and other penetrations necessary to the execution of the work of other trades.
3. Coordinate mix design and finishing of colored concrete work to assure appearance match with cast-in-place concrete included on the Structural Drawings.

1.04 ACTION SUBMITTALS

A. Product Data: Manufacturers' current catalog data and specifications for the following:
1. Formwork panels and board form liners, if used.
2. Expansion joint filler materials.
3. Color admixtures.
4. Curing compounds.
5. Other items as requested by

1. The Owner may retain, at its expense, a testing laboratory to perform material evaluation tests in accordance with Section 01 45 00 - Quality Control.
2. Testing may include slump tests and securing samples of concrete, cement, aggregates or other materials for testing. Applicable materials shall be provided by the Contractor at no additional cost to the Owner.

E. Mockups:
1. General:
   a. Mix design shall match that used on accepted sample panels and proposed for use in final construction including cement and color additive.
   b. Prepare at least one month before start of final concrete work to allow concrete to cure before observation.
   c. Concrete color and finish for mockup appearance shall match color and finish of accepted sample.
   d. Build mockups at the location indicated or, if not indicated, as selected by the Owner's Representative.
   e. Notify Owner's Representative 5 working days in advance of dates and times when mock-ups will be constructed and days when will be ready for review.
   f. Contractor shall allow for preparation of 1 comprehensive mockup and up to 2 flat paving mockups for evaluation and final approval of each concrete.
   g. Color and texture shall be approved before starting construction.
   h. Perform specified slip-resistance testing on paving mockups.
   i. Maintain final accepted mockups in an undisturbed condition as a standard for judging the completed Work.
   j. Retain samples of sands, aggregates, and colorants used in the mockups for comparison with materials used in final work.
   k. Demolish and remove mockups when directed if not incorporated into the final work.
2. Walls and Steps:
   a. Wall Size: Minimum 4 feet long by maximum height and include 2 tie holes, horizontal and vertical corner treatment, and specified texture finishes.
   b. Stair Size: Minimum 2 treads and 2 risers by 4 feet long and including safety scoring at nosing.
3. Board Formed Concrete: An on-site mockup is required for the board-formed architectural cast-in-place concrete for verification of concrete appearance using the proposed mix design. Mockup will also be used for final evaluation and approval of appearance, formwork layout, and workmanship
   a. Size: Not less than 4 foot x 4 foot and to include a typical outside corner.
   b.

1.08 FIELD CONDITIONS

A. Maintain control of concrete dust and water. Do not permit adjacent areas to be contaminated.

B. For protection of existing trees to remain, see Arborist Report on the Drawings and Section 32 01 90 – Existing Tree Protection and Maintenance.

C. Maintain control of concrete dust and water. Do not permit adjacent areas to be contaminated.

PART 2 - PRODUCTS

2.01 BASE MATERIALS

A. Aggregate: Class 2, 3/4-inch maximum aggregate base, conforming to Section 26 of California Department of Transportation (CDT) "Standard Specifications."

2.02 FORMWORK

A. General:
1. Comply with ACI 347, "Recommended Practice for Concrete Formwork," for formwork and other form-facing material requirements.
2. Furnish in largest practicable sizes to minimize number of joints unless otherwise shown on the Drawings.
3. Seal joints to prevent leakage of paste using demonstrated effective method that will not affect appearance of finished surface.
4. Forms may be reused at concealed surfaces. Forms shall not be reused for exposed concrete surfaces if there is any evidence of surface wear and defect that would impair the quality of the surface or if their reuse will exist and produce a noticeable variation in the appearance in the completed work.
5. Formwork Surface Class at Exposed Concrete: Class A. In addition to ACI 303.1 limits on form-facing panel deflection, limit concrete surface irregularities, designated by ACI 347R as abrupt or

2.03 REINFORCING

A. Materials:
1. Reinforcing Steel: Deformed billet steel bars, ASTM A615, Grade 60 for No. 5 and larger, Grade 40 for No. 4 and smaller.
2. Tie Wire: ASTM A82, black annealed.
3. Spacers, Bar Supports, and Other Accessories: In accordance with ACI 315. Galvanize metal items exposed to moisture, or use approved plastic or non-corrodible, non-staining supports.
4. Smooth Dowels for Expansion Joints: ASTM A615, Grade 40 smooth, billet-steel bars, shop painted with iron-oxide zinc-chromate primer.

B. Reinforcing steel shall be cut and bent cold to exact lengths and shapes to comply with Drawings, reviewed shop drawings, and referenced codes and standards.

C. Comply with the additional requirement shown on the Drawings.

2.04 CONCRETE MATERIALS

A. Portland Cement: ASTM C150, Type II, low alkali, and with a proven history of successful use with

1. Mix designs for concrete shall be Contractor-designed at its expense. Designs shall be prepared by a qualified agency approved by the Owner's Representative.
2. Use admixtures according to manufacturer's written instructions.
3. Ensure equipment and plant will afford accurate weighing, minimize segregation, and will efficiently handle materials.
4. Deposit concrete into final position within 90 minutes of introduction of cement.

B. Color Pigment: Add color pigment to concrete mix according to manufacturer's written instructions and to result in hardened concrete color consistent with approved mockup.

C. Waterproofing: Crystalline waterproofing powder shall be added to the concrete mix at water features at rate of 3 percent by weight of Plant cement content, unless otherwise recommended by manufacturer for mix design.
1. Waterproofing shall be added to the concrete mix at time of batching.
2. Thorough blending of the admixture throughout the concrete mix to ensure a homogeneous mixture is obtained.

D. Minimum ultimate compressive strength of concrete at 28 days is as follows:

Item	Strength	Maximum slump	Size of aggregate	Cement (# of 94 lb. sacks per yard)	W/C Ratio

B. Ties for exposed concrete surfaces shall be arranged symmetrically and shall be aligned both vertically and horizontally. Do not stagger.

C. Extend forms for all exposed concrete at least 6 inches below finish grade.

D. Do not disturb earth at bottoms of excavations for forings or foundations. Maintain these areas free of water, properly cleaned and leveled off.

E.

C. Placing:
1. Moisten earth, and spray forms and reinforcement with water before placing concrete.
2. Place concrete in continuous operation to prevent cold joints and to permit proper and thorough integration and to complete scheduled placement.
3. Hot-Weather Concreting: Conform to ACI 305 when mean daily temperature rises above 80 degrees F.
4. Use vibrators for thorough consolidation of concrete.
   a. Provide vibrators at each point of deposit during simultaneous placing to ensure timely consolidation around reinforcement, embedded items, and into corners of forms; ensure availability of spare vibrators in case of failures.
   b. Do not place vibrators against reinforcement, attach to forms, or use to spread concrete.
5. Distribute concrete in maximum 18-inch layers, unless otherwise accepted.
6. Space points of deposit to eliminate need for lateral flow.

3.05 REMOVING AND REUSING FORMS

A. Formwork for a given area shall be removed at the same time to enhance uniformity of final appearance.

B. Formwork that does not support weight of concrete may be removed after cumulatively curing at not less than 50 degrees F for 24 hours after placing concrete, provided concrete is hard enough to not be damaged by form-removal operations and provided curing and protection operations are maintained.

C. Remove forms for exposed concrete so as to avoid damage to finish. Do not use pinch bars and similar tools for prying against exposed surfaces.

D. Upon removal of forms, remove ties, wires, and similar metal items not necessary to finished work to minimum 1 inch from surface. Remove them in a way as to eliminate danger of rust stains from form-tie materials or other unprotected ferrous metals embedded in or adjacent to exposed concrete surfaces.

E. Re-use of forms will only be permitted as specified. When forms are reused, clean surfaces, remove fins and laitance, and tighten to close joints. Apply form-release agent. Align and secure joint to avoid offsets.

3.06 FINISHING FORMED SURFACES

A. Rough-Formed Finish on Unexposed Concrete: As-cast concrete texture imparted by form-facing material with tie holes and defective areas repaired and patched. Remove fins and other projections exceeding ACI 347R.

B. Formed Finish on Exposed Concrete: As-cast concrete texture imparted by form-facing material, arranged in an orderly and symmetrical manner with a minimum of seams.
1. Repair and patch tie holes and defective areas. Remove fins and other projections exceeding 1/8 inch in height.
2. Finish appearance shall match concrete on Building.

C. Related Unformed Surfaces: At tops of walls, horizontal offsets, and similar unformed surfaces adjacent to formed surfaces, strike off smooth and finish with a texture matching adjacent formed surfaces. Continue final surface treatment of formed surfaces uniformly across adjacent unformed surfaces, unless otherwise indicated.

D. Adjusting:
1. Remove projecting fins, bolts, wire, nails, and similar items not necessary for the work, or cut them back 1 inch from the surface and patch in an inconspicuous manner.

SECTION 32 33 00

SITE FURNISHINGS

PART 1 - GENERAL

1.01 SUMMARY

A. Section Includes:
1. Site furnishings and installation accessories as shown on the Drawings including, but not necessarily limited to, the following:
a. 5 Row Bleachers.
b. Baseball pitching rubbers.
c. Softball pitching rubbers.
d. Baseball/softball bases
e. Baseball/so718 27(t)-14I4uJ -2. a11w 6(a11w 6(a11wh1w 6(98 TD .002m4voH(Tw (e.)Tj /TT3 Tf 1.5

1.04 ACTION SUBMITTALS

A.

ITEM	DESCRIPTION	MANUFACTURER	MODEL NO.	QTY.	FINISH/COLOR	DISTRIBUTOR/CONTACT
Z.	Homeplate batting practice mat	Beacon Athletics	110-340-309	4	green	Beacon Athletics 800 747 5985 Beacon Athletics | The Ultimate Ballfield Resource
AA.	Infield Turf Protector-baseball	Beacon Athletics	280-107-110 15'x26x56'	1	Forest Green	Beacon Athletics 800 747 5985 Beacon Athletics | The Ultimate Ballfield Resource

END OF SECTION

SECTION 32 80 00

IRRIGATION

PART 1 - GENERAL

1.01 SUMMARY

A. Section Includes: Landscape irrigation system work is shown on the Drawings and includes, but not necessarily limited to, the following:
   1. New Booster Pump.
   2. Water backflow prevention and flow sensing system.
   3. Automatic irrigation controls and systems.
   4. Line voltage connections to the irrigation controllers and low voltage control wiring from controllers to remote control valves.

B. Work Included Under Other Sections:
   1. 120 Volt A.C. electrical stub-out for irrigation controller.
   2. Irrigation sleeves.

C. Related Requirements:
   1. Section 31 01 90 - Landscape and Site Maintenance
   2. Section 31 23 00 - Excavation and Fill
   3. Section 32 90 00 - Planting
   4. Section 33 11 00 - Domestic Water Utilities

1.02 REFERENCES

A. American Society for Testing and Materials (ASTM):
   1. D1785 - Standard Specifications for Poly (Vinyl Chloride) (PVC) Plastic Pipe, Schedules 40 and 80.
   2. D2241 - Standard Specifications for PVC Pressure-Rated Pipe (SDR Series).
   3. D2564 - Standard Specifications for Solvent Cements for (PVC) Plastic Pipe and Fittings.
   4. F2768 - Standard Specification for Modified Stub ACME Thread Joint with Elastomeric Seal in Plastic Piping Components.
   5. D2855 - Standard Practice for the Two-Step (Primer and Solvent Cement) Method of Joining Poly (Vinyl Chloride) (PVC) or Chlorinated Poly (Vinyl Chloride) (CPVC) Pipe and Piping Components with Tapered Sockets.
   6. F512 - Standard Specification for Smooth-Wall Poly (Vinyl Chloride) (PVC) Conduit and Fittings for Underground Installation.
   7. D2672 - Standard Specification for Joints for IPS PVC Pipe Using Solvent Cement.

B. National Sanitation Foundation (NSF), Requirements for Seal of Approval.

C. Plastics Pipe Institute (PPI), Recommendations for hydrostatic design stresses for PVC pipe.

D. State of California, Business and Transportation Agency, Department of Transportation (Caltrans) "Standard Specifications."

E. Permits and Fees: Contractor is responsible to obtain all required permits and pay all associated fees unless otherwise noted.

F. Irrigation Association/American Society of Irrigation Consultants, Landscape Irrigation Best Management Practices, 2014 edition.

1.03 ADMINISTRATIVE REQUIREMENTS

A. Substitutions for specified products shall be submitted for approval in accordance with Section 01 25 00 – Substitution Procedures.

B. Submittal Procedures: Action and Informational Submittals shall be submitted in accordance with Section 01 33 00 - Submittal Procedures.

C. Coordination, Sequencing, and Scheduling:
1. Contractor shall be solely responsible for coordinating, sequencing and scheduling work with applicable trades and subcontractors so as to ensure proper and timely installation of the irrigation system.
2. The entire irrigation system shall be under full automatic operations for a period of two days prior to beginning of planting. Coordinate with Section 32 90 00 – Planting.

D. Permits and Fees: Contractor is responsible to obtain all required permits and pay all associated fees unless otherwise noted.

1.04 ACTION SUBMITTALS

A. Shop Drawings: A diagrammatic drawing of proposed mainline route and equipment locations for approval by the Owner's Representative. The Drawings may be marked and used for marking layout and equipment locations.

B. Product Data: Manufacturer's literatur

C. Contractor shall record and scan and submit PDF files of full size plan set of Record Drawings (As-builts Drawings) to the Owner's representative, and two sets of color coded plans shall be produced, one for placement at or within the irrigation controller cabinet reduced to 11" x 17", and one full size set for submittal to the Owner or stored at another location selected by the Owner's Representative.
   1. Both sets shall have all the irrigation valve zone lateral lines color-coded so as to readily distinguish between adjacent zones.
   2. The color-coded copies shall then be professionally laminated in minimum 5 mil clear plastic.

1.07 QUALITY ASSURANCE

A. Unless otherwise specified, install materials in accordance with manufacturer's details, specifications and recommendations.

B. The Contractor shall be responsible to assure that the irrigation installer personally or through an authorized and competent representative, supervises the work and retains the same supervisor on the job from commencement to completion.

1.08 DELIVERY, STORAGE, AND HANDLING

A. Store PVC pipe in a neat and orderly manner fully supported and protected from sunlight.

B. Equipment and materials shall be delivered, unloaded, and handled so as to protect from damage at all times.

1.09 FIELD CONDITIONS

A. PVC shall not be cemented during wet conditions at the discretion of the Owner's Representative.

B. Trench excavation and backfilling shall not be performed during excessively wet conditions at the discretion of the Owner's Representative.

C. Water Supply: Connections to, or the installation of, the water supply shall be at the locations shown on the Drawings. Minor changes caused by actual site conditions shall be made at no additional expense to Owner.

D. Discrepancies: In the event of discrepancy, immediately notify the Owner's Representative. Do not proceed with installation or irrigation components of system in areas of discrepancy until discrepancies have been resolved.

1.10 MAINTENANCE EQUIPMENT

A. Turn-over Materials: Provide 1 each of the following to the Owner's Representative:
   1. One quick coupler attachment key equipped with standard thread hose bib for each 5 quick couplers installed on the project.
   2. One key for locking quick coupler covers for each 5 quick coupler valves installed on the project.
   3. One key for hose bib operation for each 5 hose bibs installed on the project.
   4. One set of keys to irrigation controller and other installed locking cabinets or pedestals.

B. Full set of remaining nozzles for each rotor sprinkler.

1.11 GUARANTY

A. Contractor: Provide Owner with a separate written guaranty for the entire irrigation system against defects in installation, workmanship and equipment for a period of 1 year from the date of Final Acceptance.

1. Pipe Diameter up to 6 Inches: Weld-On #705 by IPS Corporation, Low VOC PVC solvent cement for Class 200 PVC or schedule 40 PVC.
2. Pipe Diameter Larger than 6 Inches and Schedule 80: Weld-On #711 by IPS Corporation, Low VOC PVC solvent cement.
3. Flexible PVC to Rigid PVC Connections: Weld-On #795 by IPS Corporation, Low VOC PVC solvent cement.

2.11 SPRINKLER HEADS

A. Rotors, Rotators and Spray Heads: As specified on the Drawings.

B. Install with purple rotor covers or head caps if system is designed for recycled water.

2.12 TREE AND SHRUB BUBBLERS

A. Bubbler Nozzle Assemblies: As specified on the Drawings.

B. Install bubblers with purple caps if system is designed for recycled water.

2.13 ADDITIONAL MATERIALS

A. Tape:
1. General:
a. On-site buried recycled water piping shall be identified by warning tape with a minimum width of 3 inches reading “caution – recycled water” (in black or white lettering on purple background). Tape shall run continuously on top of line piping and shall be attached to piping with plastic tape banded around the warning tape and the pipe every 5 feet on center.
2. Pipe Detection Tape: 3-inch-wide, detectable tape, “Terra Tape” "Sentry Line Detectable” from Reef Industries, Inc., 713.507.4251; or equal.
a. Text: "Caution Water Line Buried Below."

B.

2. Form thrust blocks in such a manner such that concrete comes in contact only with the fittings, not over the fitting joint. Thrust blocks shall be between solid soil undisturbed and the fitting.
3. Install thrust blocks as shown on Drawings and as described above.
4. Main lines of 3 inches and 4 inches with operating pressures of 85 psi or more, and systems with a booster pump, shall have mechanical restraints at all fittings and changes of flow direction.
5. Main lines 6 inches and larger shall have ductile iron fittings with joint restraints installed at all couplings and changes of flow direction.

D. Solvent Welded Joints:
1. Assemble above ground where possible.
2. Cut square, ream, and thoroughly clean shavings and burs from pipe ends.
3. Make joint using specified primer and cement, continuously wiping off excess.
4. Allow 60 minutes of set-up time before handling and 24 hours curing before applying water pressure.

E. Threaded Joints:
1. Use Teflon tape on all pressurized, threaded plastic to plastic and plastic to metal joints.
2. Hand tighten and use only light strap-type friction wrench pressure to complete.

F. Snake pipe to provide a minimum of 1 additional foot for each 100 feet of pipe to allow for expansion and contraction.

G. Pipe shall be installed as specified and generally as shown in Drawings.

H. Cap or plug pipe openings as soon as pipes have been installed to prevent intrusions of debris.

I. Sleeves:
1. Install pipe sleeves where necessary, where shown and at all points where pipes pass through concrete or masonry. In footing, install sleeving that allows 1-inch minimum clearance around pipes.
2. Each end of sleeve shall extend a minimum of 6 inches beyond edge of paving or structure above. Provide removable non-decaying plug or cap at the end of sleeve, to prevent earth from entering pipe.

J. Thoroughly flush system prior to installing valves, screens and nozzles.

K. Install pipe detection tape and tracer wire above mainline.

3.05 EQUIPMENT AND INSTALLATION

A. Reduced Pressure Backflow Prevention Device: Install in accordance with local codes and as shown on the Drawings.

B. Master Valve:
1. Install as shown in Drawings.
2. Valve boxes shall be set plumb, flush, and square with adjacent structures.
3. Valves shall be installed in valve boxes to provide 2-inch clearance between the highest point of the valve and the bottom of the valve box lid.
4. Install valve tags in an acceptable manner indicating valve station and controller number.
5. Provide 12-inch minimum separation when valves are grouped together, and align in a straight, parallel, even, and orderly manner.
6. Locate all boxes a minimum of 10 feet from striping of any field of play.
7. Locate valves in shrub/ground cover areas whenever possible.

C. Gate Valves and Ball Valves:
1. Install as shown on the Drawings.

2. Valves shall be installed in valve boxes to provide a minimum of 2-inch clearance between the highest point of the valve and the bottom of the valve box lid.
3. Valves shall not be installed in any area that is within the athletic field of play. All valves shall be located within valve boxes set 12 inches from fencing or edge bands as shown.
4. Locate all boxes a minimum of 10 feet from striping of any field of play.

D. Remote Control Valves:
1. Install as shown in Drawings.
2. Valve boxes shall be set plumb, flush, and square with adjacent structures.
3. Valves shall be installed in valve boxes to provide 2-inch clearance between the highest point of the valve and the bottom of the valve box lid.
4. Install valve tags in an acceptable manner indicating valve station and controller number.
5. Provide 12-inch minimum separation when valves are grouped together, and align in a straight, parallel, even, and orderly manner.
6. Locate all boxes a minimum of 10 feet from striping of any field of play.
7. Locate valves in shrub/ground cover areas whenever possible.
8. Two Wire decoders, as specified, are to be located within the valve boxes with 36 inches of wire coil to allow for easy maintenanc

11. Two Wire decoder cable over 10,000 and up to 15,000 feet from controller to decoder shall be 12 gauge.
12. Distance between Two Wire Decoder and Solenoid shall be in accordance with manufacturer's specifications.
13. Install terminus ends of two wire cable with 36-inch length in 8-inch round valve box and record location of each box on the Record Drawings.
14. Install Two Wire Lightning Discharge per manufacturer's details and recommendations.

I. Rotor, rotator and Spray Heads:
1. Install as shown in Drawings.
2. Install plumb with finish grade.
3. Thoroughly flush all lines prior to installing nozzles.

J.

PART 2 - PRODUCTS

2.01 TOPSOIL

A.

2. Quantities shown on the Drawings are for the Contractors convenience only. Contractor shall provide plant material to fulfill the intent of th

2.07 TURF SOD

A. Harvest and Delivery:
1. Harvest from source and deliver to project site within 24 hours.
a. Deliver only as much sod as can be installed in one day's work.
b. Sod not transplanted within this time period shall be reviewed prior to installation.
2. Comply with requirements in "Specifications for Turfgrass Sod Materials" and "Specifications for Turfgrass Sod Transplanting and Installation" from Turfgrass Producers International's (TPI) "Guideline Specifications to Turfgrass Sodding."
3. Protect sod from breakage and drying.

B. Sod shall be as follows:
1. Tiffway II Hybrid Bermuda
2. Sod shall have a 3/4 inch cut or thickness.
3. Sod shall be large roll cut.
4. Sod shall have a peat or sand / peat base.

C. Source: Delta Bluegrass, Western Sod Farms, Pacific Sod, or equal.

2.08 HYDROSEED SLURRY

A. Hydroseed slurry shall contain the following (or acceptable equal), thoroughly mixed and applied per acre. Method for hydroseeding shall be a two-step hydraulic straw treatment as follows:

Step One		
	Lbs/acre	hydroseed mix
o	2000	Hydro straw™ straw and tack mulch
o	1000	7-2-3 Biosol
o	As specified	Native grass and wildflower seed mix
o	60	AM 120 mycorrhizal inoculant
Step Two		
	Lbs/acre	hydroseed mix
o	2000	Hydro straw™ straw and tack mulch

B. Hydroseed slurry shall contain green dye at a rate common to the industry so that hydroseed coverage can be confirmed visually from a distance.

C. Equipment used for application of hydroseed slurry shall be a commercial type hydro-seeder and have built-in agitation system with an operational capacity sufficient to agitate, suspend and homogeneously mix slurry. Tank capacity shall be a minimum of 1,500 gallons and shall be mounted on a truck to allow access to site. Distribution lines shall be large enough to prevent stoppage and allow for even distribution of slurry over the site. Pump shall be able to generate 150 psi at the nozzle.

D. During first week after planting, water daily or more frequently as necessary to maintain moist soil to a minimum depth of 1-1/2 inches below sod.

2.09 HERBICIDES

A. Pre-Emergent: "Ronstar-G" pellet, "Surflan" liquid, or equal.

B. Other Herbicides: Submit for review and acceptance by Owner's Representative prior to use.

2.10 ADDITIONAL MATERIALS

A. Water: Clean, fresh, and free of substances or matter which could inhibit vigorous growth of plants.

B. General: Products and materials shall be new, first quality as acceptable to the Owner's Representative.

C. Tree Stakes and Ties: As shown and specified on the Drawings.

D. Header Board: As shown and specified on the Drawings.

E. Root Barriers: Model #UB 24-2 "Universal Barrier" by Deep Root Partners L.P, 800-458-7668, or equal.

F.

3.03 SOIL PREPARATION AND FINISH GRADES

A. Soil Preparation:
   1. Thoroughly roto-till the following additives into the top 6 inches of planting area soil at the following rates per 1,000 square feet:
      a. Soil Amendment: 6 Cubic Yards.
      b. Soil Conditioner: 200 Pounds.
      c. Pre-Plant Fertilizer: 35 Pounds.
      d. Soil Sulfur: 20 Pounds.
   2.

4. Once fully loaded, the complete slurry shall be agitated for 3-5 minutes to allow for uniform mixing.

C. Apply hydroseed evenly and uniformly over areas to be seeded at rates specified. Apply in a sweeping motion to form a uniform application and form a mat at the specified rates.

D. Seeding shall occur before first germinating rains in the fall.

E. If mixture remains in the tank for more than 8 hours it shall be removed from the job site.

F. Remove or clean areas not intended to receive hydroseed treatment.

3.05 SOD INSTALLATION

A. General:
1. Soil preparation and fine grading shall be as specified.
2. Prior to sod installation, roll turf bed until a smooth, firm surface with uniform grade has been produced.
3. The turf bed shall be reviewed and accepted by the Owner's Representative prior to sod installation.

B. Placement:
1. Sod shall be unrolled into place with careful attention to tight joints with no overlapping or stretching.
2. Stagger the joints in each new row like rows of bricks with a minimum 18 inch minimum stagger. Use a sharp knife for shaping around trees, flower beds or borders. Immediately after placement, soak sod areas with water.
3. Roll sod after watering to smooth out bumps and pockets, and roll again if sod is not even.
4. Water frequently for the first 10 to 14 days with enough water to saturate soil to a depth of 4 inches.
5. Do not allow sod dry out.

C. Provide and install temporary fencing around completed sod areas if not protected by other fencing. Use 6 foot high temporary fence for protection.

D. Refer to Section 31 0190 – Landscape and Site Maintenance for mowing and maintenance procedures. As applicable, the Contractor shall remove sod, rake any areas that have been rutted from mowers or otherwise damaged, and replace sod to the satisfaction of the Owner's Representative.

E. Until project Final Acceptance, should it become evident that certain sod areas have not grown, re-sod the areas immediately with sod of the same yaoll

33 11 00

DOMESTIC WATER UTILITIES

PART 1 - GENERAL

1.01 SUMMARY

A. Section Includes: Domestic water and fire system work shown on the Drawings including, but is not necessarily limited to, the following:
   1. Intermediate staking and layout for domestic water system.
   2. Pipes, fittings, valves, valve boxes, connections, and fire hydrants for systems.
   3. Field testing and disinfection.

B. Related Requirements:
   1. Section 32 11 00 - Base Courses
   2. Section 32 23 00 - Excavation and Fill
   3. Section 32 80 00 - Irrigation
   4. Section 32 90 00 - Planting

1.02 REFERENCES

A. American Water Works Association: Current edition of Standards as specified.

B. California Plumbing Code: Current Edition.

C. State of California, Business and Transportation Agency, Department of Transportation (Caltrans) "Standard Specifications."

1.03 ADMINISTRATIVE REQUIREMENTS

A. Submittal Procedures: Action and informational Submittals shall be submitted in accordance with Section 01 33 00 - Submittal Procedures.

B. Sequence and Scheduling:
   1. Refer to other Contract Documents, determine the extent and character of related work, and properly coordinate work specified herein with that described elsewhere to produce a complete, operational installation.
   2. Contractor shall be solely responsible for coordinating, sequencing, and scheduling work with other trades and subcontractors to insure proper and timely performance of the work under this Section.

1.04 ACTION SUBMITTALS

A. Product Data: Manufacturer's "cut-sheets" for products proposed for use.

1.05 INFORMATIONAL SUBMITTALS

A. Certification that ductile iron pipe supplied for this Project has been manufactured in compliance with all requirements of AWWA C151.

B. Certification that PVC pipe supplied for this project has been manufactured in compliance with all requirements of AWWA C900.

1.06 CLOSEOUT SUBMITTALS

A. Project Record Drawings that provide accurately record locations of utilities remaining, re-routed utilities, new utilities, and newly discovered utilities by horizontal dimensions, elevations, inverts, and slope gradients. Comply with additional requirements specified in Section 01 78 39 – Project Record Documents.

B. Warranty as specified.

C. Results of field testing of completed system.

D. Certificate of Compliance for disinfection.

1.07 QUALITY ASSURANCE

A. Unless otherwise specified, inst

1. Pipe materials for domestic and fire water lines shall be in conformance with the California Plumbing Code and local governing agencies.
2. Plans and details, if shown, are schematic in nature and do not necessarily identify all fittings and appurtenances required to provide a complete installation. The Contractor is responsible for providing complete and functional systems.
3. Materials and procedures not specifically addressed herein shall comply with the appropriate AWWA standard.
4. Materials proposed for use shall be in a new, "first class" condition unless otherwise noted.

B. Water Lines 3 Inches and Greater Diameter:
1. Ductile Iron Pipe (DIP): Cement lined, of domestic manufacturer complying with ANSI/AWWA C151/A21.5, minimum Class 52; "Tyton Joint" by U.S. Pipe, Pacific States, or acceptable equal.
   a. Cement mortar lining shall comply with ANSI/AWWA C104/A21.4.
   b. Buried ductile iron pipe and fittings shall be wrapped in an 8-mil thick polyethylene film sleeve.
2. Polyvinyl Chloride Pipe (PVC): Conform to AWWA C900, Class 200, of domestic manufacture, and meeting cast iron outside diameter sizes; "C900" Series North American Specialty Products, JM Eagle, or acceptable equal.
   a. Pipe shall be furnished with integral bells.
   b. Spigot end pipe with separate double hub couplings is not acceptable.

C. Water Lines 2 Inches and Smaller Diameter: One of the following.
1. Annealed (soft) Type "K" copper (Cu).
2. Polyvinyl chloride (PVC) conforming to ASTM D1785, Schedule 80 PVC, of domestic manufacture, and meeting cast iron outside diameter sizes; ASTM D1785 Series North American Specialty Products, JM Eagle, or acceptable equal.
   a. Pipe shall be furnished with integral bells.
   b. Spigot end pipe with separate double hub couplings is not acceptable.

D. Couplings and Sleeves:
1. General:
   a. Couplings and sleeves shall be a minimum of 300-psi working pressure rated unless except as otherwise noted.
   b. Couplings and sleeves shall be mechanical joint type.
   c. Couplings, sleeves, and accessories shall be of domestic manufacture; "Trim Tyton" by U.S. Pipe, Union Foundry, Tyler Pipe, and Couplings, or acceptable equal.
2. DIP and PVC Pipe 3 Inches thru 12 Inches:
   a. Unless otherwise noted, couplings and sleeves for DIP and PVC shall be ductile iron conforming to AWWA C153, and shall be 350 psi working pressure rated.
   b. Unless otherwise noted, flanges on all DIP spools shall conform to ANSI/AWWA C115/A21.15.
3. PVC Pipe 2 1/2 Inches and Smaller: Schedule 40, solvent-weld PVC socket couplings.
4. Copper Tubing: "Mueller 110" compression connections by Mueller Company Ltd., or acceptable equal.

E. Gate Valves:
1. Use gate valves designed for a working pressure of not less than 150 psi.
2. Provide connections as required for the piping in which they are installed.
3. Provide an arrow on the operating nut or wheel, cast in metal, indicating direction of opening.

F. Thrust Blocks: Class "A" concrete construction with dimensions conforming to the California Plumbing Code.

G. Valve Boxes:
1. Size: 10 inches round boxes for gate valves.
2. Box lid shall be labeled with "water" and shall be bolted down.

3. Boxes located in landscape areas shall be round plastic; Carson model 910-10 with 910-4 lid, or equal.
4. Boxes located in paving shall be concrete with concrete lid.

H. Pipe Detection Tape: 3 inch wide, detectable type, "Terra Tape" "Sentry Line Detectable" from Reef Industries, Inc., 713.507.4251; or equal.
1. Text: "Caution Water Line Buried Below."

I. Tracer Wire: Polyethylene insulated, copper clad steel; "SoloShot XTreme Tracer Wire" by Copperhead Industries, LLC. 877-726-5644, or equal.

PART 3 - EXECUTION

3.01 EXAMINATION

A. Prior to starting work, test and verity that water pressure levels meet the domestic water system requirements. Notify the Owner's Representative immediately of any discrepancies and re-direct work to avoid delay.

B. The utility plan and the piping details on the Drawings are diagrammatic. Pipe lines shown parallel in the Drawings may be placed in a common trench, provided that a minimum horizontal distance of 6 inches is maintained between buried lines, except for sanitary sewer lines, which require 10 feet horizontal clearance.

3.02 HANDLING

A. Handle pipe accessories so as to ensure delive

3.07 SETTING VALVES AND VALVE BOXES

A. Center valve boxes on the valves, setting plumb.

B. Tamp earth fill around each valve box to a distance of four feet on all sides, or to the undisturbed trench face if less than four feet.

C. Tighten mechanical joints, and fully open and close each valve to assure that all parts are in working condition.

3.08 THRUST BLOCKS

A. Provide and install thrust blocks in accordance with California Plumbing Code requirements and installation guidelines.

3.09 TESTING, INSPECTING, AND DISINFECTION

A. General:
1. Do not allow or cause the work of this Section to be covered up or enclosed until after it has been completely inspected, tested, and has been accepted by the Owner's Representative and governing authorities when applicable.
2. Perform tests and disinfection in a manner acceptable to governmental agencies having jurisdiction.

B. Testing:
1. Except for joint material setting, or where concrete reaction backing necessitates a five day delay, pipelines joints, or couplings may be subjected to hydrostatic pressure, inspected, and tested for leakage at any time after partial completion of backfill.
2. Testing of water service shall be in accordance with the requirements of AWWA C600 for hydrostatic testing.
3. Contractor shall keep records of each piping test, including date and time of test, name of witnessing Owner Representative, test pressure, description of piping tested, and clarifying comments including those related to leaks and repairs made.
4. Tests shall last 4 hours and be tested at 200 psi.

C. Disinfection:
1.

F. Install pipe detection tape and reinforced tracer wire above pressurized lines.

3.11 DEMONSTRATION

A. Contractor shall instruct Owner's personnel in complete proper operation of domestic water system per prior to Contract closeout.

3.12 FINAL REVIEW

A. Provide Owner's Representative with specified closeout submittals prior to Final Review.

END OF SECTION

1.04 ACTION SUBMITTALS

A. Product Data: Manufacturers' data sheets for the following:
   1. Piping materials and fittings.
   2. Special pipe couplings.
   3. Precast concrete cleanouts and box covers.

1.05 INFORMATIONAL SUBMITTALS

A. Design Mix Reports and Calculations: Submit for each class of cast in place concrete.

B. Field Test Reports: Indicate and interpret test results for compliance with specified performance.

1.06 QUALITY ASSURANCE

A. Control of Work: Conform to Section 5 of the Standard Specifications.

B. Control of Materials: Conform to Section 6 of the Standard Specifications.

1.07

necessary to bleed off the air to tighten or repair faulty plug, a new 5-minute interval shall be allowed after the pipeline has been refilled.

8. After the stabilization period, adjust the air pressure to 3.5 psi and shut-off or disconnect the air supply. Observe the gage until the air pressure reaches 3.0 psi. At 3.0 psi commence timing with a stopwatch which is allowed to run until the pressure drops to 2.5 psi at which time the stopwatch is stopped. The time required, as shown on the stopwatch, for a pressure loss of 0.5 psi is used to compute the air loss.
9. If the time, in minutes and seconds, for the air pressure to drop from 3.0 to 2.5 psi is greater than that shown in the following table for the designated pipe size, the section undergoing test shall have passed and shall be presumed to be free of defects. The test may be discontinued at that time.
10. If the time, in minutes and seconds, for the 0.5 psi drop is less than that shown in the following table for the designated pipe size, the section of pipe shall not have passed the test; therefore, adequate repairs must be made and the line retested.

Requirements for Air Testing:		
Pipe size in Inches	Time	
	Minutes	Seconds
4	2	32
6	3	50
8	5	06
10	6	22
12	7	39

SECTION 33 40 00

STORM DRAINAGE UTILITIES

PART 1 - GENERAL

1.01 SUMMARY

A. Section Includes: Storm drainage system improvements and related work as shown on the Drawings and specified including, but is necessarily limited to, the following:
   1. Pipe and fittings.
   2. Nonpressure transition couplings.
   3. Expansion joints and deflection fittings.
   4. Backwater valves.
   5. Cleanouts.
   6. Drains.
   7. Channel drainage systems.
   8. Catch basins.
   9. Stormwater inlets.
   10. Stormwater treatment systems.
   11. Pipe outlets.

B. Related Requirements:
   1. Section 31 20 00 - Earth Moving
   2. Section 31 23 00 - Excavation and Fill
   3. Section 32 11 00 - Base Courses
   4. Section 32 32 15 - Landscape Concrete
   5. Section 32 33 00 - Site Furnishings
   6. Section 33 10 10 - Domestic Water Utilities

1.02 REFERENCES

A. American Society for Testing and Materials (ASTM):
   1. C478: Standard Specification for Circular Precast Reinforced Concrete Manhole Sections.
   2. C923: Standard Specification for Resilient Connectors Between Reinforced Concrete Manhole Structures, Pipes, and Laterals.
   3. D2321: Standard Practice for Underground Installation of Thermoplastic Pipe for Sewers and Other Gravity-Flow Applications.
   4. D2412: Standard Test Method for Determination of External Loading Characteristics of Plastic Pipe by Parallel-Plate Loading.
   5. D2729: Standard Specification for Poly (Vinyl Chloride) (PVC) Sewer Pipe and Fittings.
   6. D3034: Type PSM Poly (Vinyl Chloride) (PVC) Sewer Pipe and Fittings.
   7. D3350: Standard Specification for Polyethylene Plastics Pipe and Fittings Materials.
   8. D4101: Standard Specification for Polypropylene Injection and Extrusion Materials.

B. California Building Code, Current Edition.1.5(ionu 8 an.4(o)Mon and Exse26pUNion (B."Tj /TTMh92(e)-2.6A TD
3.

PART 2 - PRODUCTS

2.01 PIPE AND FITTINGS

A. General:
1. Pipe and fittings shall be clearly and permanently marked to identify manufacturer, type, class, or schedule and NSF approval as applicable.
2. Unless otherwise noted, Contractor has option of using either CHDPE or PVC pipe as specified.

B. Corrugated High Density Polyethylene (CHDPE) Pipe: Pipe shall be smooth wall, perforated and solid with an integrally formed smooth waterway; "N-12 "drainage pipe by Advanced Drainage Systems, Inc., 510-913-2211, or equal.
1. Nominal sizes shall have a full circular cross section with an outer corrugated pipe wall and an essentially smooth inner wall (waterway).
2. Corrugations may be either annular or spiral.
3. Sizes shall conform to the AASHTO classification "Type S."
4. Pipe manufacturer for this specification shall comply with the requirements for test methods, dimensions, and markings found in AASHTO Designations M252 and M294.
5. The minimum parallel plate stiffness values when tested in accordance with ASTM D2412 shall be as follows:

Diameter	Pipe Stiffness
4 inch (100 mm)	50 psi (340 kPa)
6 inch (150 mm)	50 psi (340 kPa)
8 inch (200 mm)	50 psi (340 kPa)
10 inch (250 mm)	50 psi (340 kPa)
12 inch (300 mm)	50 psi (340 kPa)

1. Size: 1.5 inches by 12 inches wide.
2. Couplers, Wyes, Tees, End Caps, and Pipe Adapters: “AdvanEDGE” components.

G. Perforated Pipe for Slit Sand Drainage System: Spiral corrugated, single wall, 2-inch diameter;” Turf Flow” by Hancor, Inc., 888-367-7473 as specified, or equal.

2.02 DRAINAGE STRUCTURES

A. Precast Catch Basins:
1. General:
   a. Grates in paved areas shall conform to ADA Standards for Accessible Design.
   b. All catch basins to have locking mechanism or screw down grate to frame.
   c. Provide two grade rings at each catch basin.
2. 12-Inch Basin: “CB12” supplied by Carlton Precast – US Concrete, or equal.
   a. Grating: Round, galvanized steel, ADA compliant, lockable, and meeting AASHTO H20 heavy-duty loading, or equal.

Sieve Size	USGA Spec
	Individual % Retained
#4 (4.75mm)	0
#10 (2mm)	0
#18 (1mm)	<5